

SECTION 905 -- PROPOSAL (CONTINUED)

I (We) further propose to execute the attached contract agreement (Section 902) as soon as the work is awarded to me (us), and to begin and complete the work within the time limit(s) provided for in the Specifications and Advertisement. I (We) also propose to execute the attached contract bond (Section 903) in an amount not less than one hundred (100) percent of the total of my (our) part, but also to guarantee the excellence of both workmanship and materials until the work is finally accepted.

I (We) enclose a certified check, cashier's check or bid bond for **five percent (5%) of total bid** and hereby agree that in case of my (our) failure to execute the contract and furnish bond within Ten (10) days after notice of award, the amount of this check (bid bond) will be forfeited to the State of Mississippi as liquidated damages arising out of my (our) failure to execute the contract as proposed. It is understood that in case I am (we are) not awarded the work, the check will be returned as provided in the Specifications.

Bidder acknowledges receipt of and has added to and made a part of the proposal and contract documents the following addendum (addenda):

ADDENDUM NO. 1 DATED 11/5/2014 ADDENDUM NO. 3 DATED 11/17/2014
 ADDENDUM NO. 2 DATED 11/14/2014 ADDENDUM NO. DATED

Number	Description
1	Revised Table of Contents; Add NTB No. 4329; NTB No. 5252 replaces NTB No. 5045; Add NTB Nos. 5264, & 5265; Add SP No. 907-810-4; Revised SP No. 907-824-1; Revised Bid Items; Revised or Added Plan Sheet No. 8001; Amendment EBS Download Required.
2	Revised Table of Contents; Add NTB No. 5268; Revised Bid Items; Amendment EBS Download Required.
3	Revised Table of Contents; Revised NTB Nos. 5204, & 5268; Add SP Nos. 907-237-4, & 907-246-3; Revised Bid Items; Amendment EBS Download Required.

TOTAL ADDENDA: 3
 (Must agree with total addenda issued prior to opening of bids)

Respectfully Submitted,

DATE _____

_____ Contractor

BY _____ Signature

TITLE _____

ADDRESS _____

CITY, STATE, ZIP _____

PHONE _____

FAX _____

E-MAIL _____

(To be filled in if a corporation)

Our corporation is chartered under the Laws of the State of _____ and the names, titles and business addresses of the executives are as follows:

_____	President	_____	Address
_____	Secretary	_____	Address
_____	Treasurer	_____	Address

The following is my (our) itemized proposal.

Revised 09/21/2005

BR-0015-01(120) / 106487301

Adams County(ies)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

TABLE OF CONTENTS

PROJECT: BR-0015-01(120) / 106487301 – Adams County

901--Advertisement

904--Notice to Bidders:

- Governing Specifications - # 1
- Fiber Reinforced Concrete - # 640
- Errata & Modifications to 2004 Standard Specifications - # 1405
- Federal Bridge Formula - # 1928
- Status of ROW w/ attachments - # 2382
- Non-Quality Control / Quality Assurance Concrete - # 2818
- Reduced Speed Limit Signs - # 2937
- Alternate Asphalt Mixture Bid Items - # 3039
- Temporary Traffic Paint - # 3131
- Type III Barricade Rails - #3655
- Petroleum Products Base Price - # 3893
- Disadvantaged Business Enterprise, w/ Supplement - # 4103
- Safety Apparel - # 4214
- Knee Braces - # 4329
- Alternate Crushed Stone Base Bid Items - # 4473
- DBE Forms, Participation and Payment - # 4488
- Warm Mix Asphalt (WMA) - # 4524
- Electronic Addendum Process - # 4526
- Manual on Uniform Traffic Control Devices (MUTCD) - # 4565
- DUNS Requirement for Federal Funded Projects - # 4566
- Payroll Requirement - # 4661
- Questions Regarding Bidding - # 5044
- Adjustments for Bituminous Materials - # 5050
- Contractor Correspondence - # 5053
- Contract Time - # 5203
- Specialty Items - # 5204
- Pre-Bid Meeting - # 5205
- Truss Monitoring Member Forces - # 5219
- Lane Closure Restrictions - # 5236
- Terminal End Sections - # 5252
- Pre-Bid Meeting Minutes - # 5264
- Additional Construction Requirements - # 5265
- Pay Item Correction - # 5268

906: Required Federal Contract Provisions -- FHWA 1273, w/ Supplements

907-101-4: Definitions

907-102-10: Bidding Requirements and Conditions

907-103-8: Award and Execution of Contract

907-104-5: Scope of Work

907-105-7: Control of Work, w/ Supplement

907-107-13: Legal Relations & Responsibility to Public

907-108-36: Prosecution and Progress

907-109-6: Measurement and Payment, w/ Supplement

907-110-2: Wage Rates

- CONTINUED ON NEXT PAGE -

- 907-213-2: Agricultural Limestone
- 907-216-1: Solid Sodding
- 907-226-2: Temporary Grassing
- 907-227-10: Hydroseeding
- 907-230-10: Tree and Shrub Planting
- 907-233-1: Tree Bark Mulch
- 907-237-4: Wattles
- 907-246-3: Sandbags & Rockbags
- 907-304-13: Granular Courses
- 907-401-2: Hot Mix Asphalt (HMA), w/ Supplement
- 907-401-6: Warm Mix Asphalt (WMA)
- 907-403-4: Hot Mix Asphalt (HMA), w/ Supplement
- 907-403-12: Warm Mix Asphalt (WMA)
- 907-407-2: Tack Coat
- 907-618-13: Temporary Construction Signs
- 907-619-5: Changeable Message Signs
- 907-626-3: Thermoplastic Markings
- 907-626-25: Thermoplastic Traffic Markings
- 907-681-2: Submittal Data
- 907-682-13: Roadway Lighting System
- 907-699-5: Construction Stakes
- 907-701-5: Hydraulic Cement, w/ Supplement
- 907-702-5: Specifications for Bituminous Materials
- 907-703-11: Aggregates
- 907-710-1: Fast Dry Solvent Traffic Paint
- 907-711-4: Synthetic Structural Fiber Reinforcement
- 907-713-3: Admixtures for Concrete
- 907-714-8: Miscellaneous Materials
- 907-715-4: Roadside Development Materials
- 907-720-2: Pavement Marking Materials
- 907-804-13: Concrete Bridges and Structures, w/ Supplement
- 907-810-4: Repairs to Knee Braces at Truss Contraction Joints
- 907-824-1: Bridge Repair

SECTION 905 - PROPOSAL, PROPOSAL BID ITEMS, COMBINATION BID PROPOSAL,
CERTIFICATION OF PERFORMANCE - PRIOR FEDERAL-AID CONTRACTS,
CERTIFICATION REGARDING NON-COLLUSION, DEBARMENT AND SUSPENSION, (2)
SECTION 902 - CONTRACT FORM,
SECTION 903 - CONTRACT BOND FORMS,
FORM -- OCR-485.

(REVISIONS TO THE ABOVE WILL BE INDICATED ON THE SECOND SHEET
OF SECTION 905 AS ADDENDA)

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 5204

DATE: 11/17/2014

SUBJECT: Specialty Items

PROJECT: BR-0015-01(120) / 106487301 - Adams County

Pursuant to the provisions of Section 108, the following work items are hereby designated as "Specialty Items" for this contract. Bidders are reminded that these items must be subcontracted in order to be considered as specialty items.

CATEGORY: CURBING, SIDEWALKS, GUTTERS

Line No	Pay Item	Description
0190	609-D007	Combination Concrete Curb and Gutter Type 2 Modified

CATEGORY: EROSION CONTROL

Line No	Pay Item	Description
0110	211-C001	Topsoil for Plant Holes, Contractor Furnished
0120	219-A001	Watering
0130	221-A001	Portland Cement Concrete Paved Ditch
0142	234-A001	Temporary Silt Fence
0360	907-213-A001	Agricultural Limestone
0370	907-216-B004	Solid Sodding, Bermuda
0380	907-226-A001	Temporary Grassing
0432	907-237-A003	Wattles, 20"
0434	907-246-B001	Rockbags

CATEGORY: GUARDRAIL, GUIDERAIL

Line No	Pay Item	Description
0170	606-B023	Guard Rail, Remove and Replace Guard Rail & Posts
0180	606-E002	Guard Rail, Terminal End Section, Flared

CATEGORY: LANDSCAPING

Line No	Pay Item	Description
0140	232-A001	Fertilizer for Woody Plant Material
0390	907-230-A118	Shrub Planting, Indian Hawthorn
0400	907-230-B047	Tree Planting, Live Oak
0410	907-230-B087	Tree Planting, Crape Myrtle
0420	907-233-A001	Tree Bark Mulch, Type III
0430	907-233-A002	Tree Bark Mulch, Type V

CATEGORY: LIGHTING, ALUMINUM TRUSSED ARM

Line No	Pay Item	Description
0330	682-A036	Underground Branch Circuit, AWG 8, 3 Conductor
0340	684-A007	Pole Foundation, 30" Diameter
0350	686-A001	Relocation of Existing Lighting Assemblies
0580	907-682-E001	Underground Junction Box With Concrete Pad

CATEGORY: PAVEMENT STRIPING AND MARKING

Line No	Pay Item	Description
0320	627-C001	Red-Clear Reflective Raised Markers
0470	907-626-A002	4" Thermoplastic Traffic Stripe, Skip White
0480	907-626-A003	6" Thermoplastic Traffic Stripe, Skip White
0490	907-626-C002	4" Thermoplastic Edge Stripe, Continuous White
0500	907-626-C004	6" Thermoplastic Edge Stripe, Continuous White
0510	907-626-F002	4" Thermoplastic Edge Stripe, Continuous Yellow
0520	907-626-F004	6" Thermoplastic Edge Stripe, Continuous Yellow
0530	907-626-G002	Thermoplastic Detail Stripe, White, 4" Equivalent Length
0540	907-626-G003	Thermoplastic Detail Stripe, Yellow, 4" Equivalent Length
0550	907-626-G004	Thermoplastic Detail Stripe, White
0560	907-626-G005	Thermoplastic Detail Stripe, Yellow
0570	907-626-H004	Thermoplastic Legend, White

CATEGORY: SURVEY AND STAKING

Line No	Pay Item	Description
0590	907-699-A002	Roadway Construction Stakes

CATEGORY: TRAFFIC CONTROL - TEMPORARY

Line No	Pay Item	Description
0210	619-A1007	Temporary Traffic Stripe, Continuous White, Type 1 Tape
0220	619-A2007	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape
0230	619-D1001	Standard Roadside Construction Signs, Less than 10 Square Feet
0240	619-D2001	Standard Roadside Construction Signs, 10 Square Feet or More
0250	619-E1001	Flashing Arrow Panel, Type C
0260	619-F3002	Delineators, Median Barrier Mounted, Yellow
0270	619-G4001	Barricades, Type III, Single Faced
0280	619-G5001	Free Standing Plastic Drums
0290	619-G7001	Warning Lights, Type "B"
0300	619-J1002	Impact Attenuator, 50 MPH
0460	907-619-E3001	Changeable Message Sign

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SECTION 904 - NOTICE TO BIDDERS NO. 5268

CODE: (SP)

DATE: 11/13/2014

SUBJECT: Pay Item Correction

PROJECT: BR-0015-01(120) / 106487301 – Adams County

The Bidder's attention is called to the Summary of Quantities in the Contract Plans. The quantity shown, 337 LF, for Pay Item 615-B001, Precast Concrete Median Barrier, is in error. The correct quantity is 5,055 LF. The bid sheets have been corrected to reflect this change.

The Bidder's attention is called to the Summary of Quantities in the Contract Plans. Pay Items 234-A001, Temporary Silt Fence, and 907-237-A003, 20" Wattles, and 907-246-3, Rockbags were inadvertently omitted from the plans. The bid sheets have been corrected to reflect this change.

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

| SPECIAL PROVISION NO. 907-237-4

CODE: (SP)

| DATE: 03/13/2012

SUBJECT: Wattles

Section 907-237, Wattles, is hereby added to and made a part of the 2004 Edition of the Mississippi Standard Specifications for Road and Bridge Construction as follows.

SECTION 907-237 - WATTLES

907-237.01--Description. This work consists of furnishing, constructing and maintaining wattles for the retention of soil around inlets, swale areas, small ditches, sediment basins and other areas as necessary. Also, the work includes removing and disposing of the wattles and silt accumulations.

Measurement and payment for wattles will be made only when a pay item is included in the bid schedule of the proposal. The quantity is estimated for bidding purposes only and will be dependent upon actual conditions which occur during construction of the project.

| **907-237.02--Materials.** Wattles used around inlets shall have a diameter of twelve inches (12") and a length adequate to meet field conditions. Wattles used at other locations shall have a diameter of twenty inches (20") and a length adequate to meet field conditions. **The minimum diameter for the above wattle sizes shall be one inch (1") less than the specified diameter.**

The stakes used in securing the wattles in place shall be placed approximately three feet (3') apart throughout the length of the wattle. Stakes shall be wooden and of adequate size to stabilize the wattles to the satisfaction of the Engineer.

In addition to the requirements of this specifications, wattles shall be listed on the Department's "Approved Sources of Materials".

907-237.03--Construction Requirements.

907-237.03.1--General. The wattles shall be constructed at the locations and according to the requirements shown on the erosion control plan.

907-237.03.2--Maintenance and Removal. The Contractor shall maintain the wattles and remove and dispose of silt accumulations.

When the wattles are no longer needed, they shall be removed and the Contractor shall dispose of silt accumulations and treat the disturbed areas in accordance with the contract requirements.

907-237.04--Method of Measurement. Wattles of the size specified will be measured per linear foot.

907-237.05--Basis of Payment. Wattles, measured as prescribed above, will be paid for at the contract unit price per linear foot, which price shall be full compensation for installation, maintaining and removal of the wattles, the removal and disposal of silt accumulations and any required restoration of the disturbed areas.

Payment will be made under:

907-237-A: Wattles, Size

- per linear foot

MISSISSIPPI DEPARTMENT OF TRANSPORTATION

SPECIAL PROVISION NO. 907-246-3

CODE: (SP)

DATE: 11/08/2010

SUBJECT: Sandbags and Rockbags

Section 907-246, Sandbags and Rockbags, is hereby added to and made a part of the 2004 Edition of the Mississippi Standard Specifications for Road and Bridge Construction as follows.

SECTION 907-246 -- SANDBAGS AND ROCKBAGS

907-246.01--Description. This item of work shall consist of the furnishing, installing, and maintaining sandbags and rockbags for the purpose of temporary erosion control by intercepting and slowing the flow of sediment-laden runoff water, or for use as a temporary dam.

907-246.02--Materials. The filler material for sandbags shall consist of a fine aggregate meeting the requirements of Subsection 703.02. The filler material for rockbags shall consist of a size 57 aggregate meeting the requirements of Subsection 703.03.

The bag material shall be woven polypropylene, polyethylene or polyamide fabric with a minimum unit weight of four (4) ounces per square yard. The bags shall be a minimum of 21 inches in length, 12 inches in width, and four (4) in thickness when filled.

907-246.03--Construction Requirements. Sandbags and rockbags shall be used to construct a berm/dam which will intercept sediment-laden storm water runoff from disturbed areas, create a retention pond, detain sediment, and release water in sheet flow. Sand or rock shall be placed in the bag so that at least the top six (6) inches of the bag is unfilled to allow for proper tying of the open end. Any subsequent rows of bags shall be offset one-half the length of the preceding row to provide a layered brick-type arrangement.

The sandbag and rockbag berm/dam installation shall be maintained in good condition by the Contractor. All necessary work and materials to maintain the integrity of the installation shall be provided until earthwork construction is complete and permanent erosion-control features are in place. The maintenance of the bags will not be paid for separately and will be included in the cost for sandbags or rockbags.

907-246.04--Method of Measurement. Sandbags and rockbags will be measured per linear foot or each.

Sandbags and rockbags measured by the linear foot shall be in accordance with the details in the erosion control drawing. The length of the sandbag or rockbag berm/dam will be measured end-to-end along the cross-section of the ditch in accordance with the erosion control drawing.

907-246.05--Basic of Payment. Sandbags and rockbags, measured as prescribed above, will be

paid for per linear foot or each, which prices shall be full compensation for furnishing bags, [fine aggregate](#), [size 57 aggregate](#), placement of bags, maintenance of the installation, removal and disposal of the sediment deposits and removal after construction has been completed, and for all labor, tools, equipment and incidentals necessary to complete the work.

Payment will be made under:

907-246-A: Sandbags - per linear foot or each

[907-246-B: Rockbags](#) - per linear foot or each

U29 & U49 Pin & Link Replacement at US 84 WB Mississippi River Bridge, known as Federal Aid Project No. BR-0015-01(120) / 106487301 in Adams County.

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
Roadway Items					
0010	201-A001		1	Lump Sum	Clearing and Grubbing
0020	202-B038		89	Linear Feet	Removal of Curb, All Types
0030	202-B053		37	Linear Feet	Removal of Guard Rail Including Post, Blockouts & Hardware
0040	202-B057		1	Each	Removal of Inlets, All Sizes
0050	202-B061		2	Each	Removal of Low Mast Lighting Foundation
0060	202-B076		24,990	Linear Feet	Removal of Traffic Stripe
0070	202-B078		1,412	Square Yard	Removal of Pavement, All Types and Depths
0080	202-B263		1,280	Linear Feet	Removal of Underground Electric Wire
0090	203-EX017	(E)	1,249	Cubic Yard	Borrow Excavation, AH, FME, Class B9
0100	203-G003	(E)	1,249	Cubic Yard	Excess Excavation, FM, AH
0110	211-C001	(E)	65	Cubic Yard	Topsoil for Plant Holes, Contractor Furnished
0120	219-A001		66	Thousand Gallon	Watering [\$20.00]
0130	221-A001	(S)	72	Cubic Yard	Portland Cement Concrete Paved Ditch
0140	232-A001		1	Thousand	Fertilizer for Woody Plant Material
0142	234-A001		200	Linear Feet	Temporary Silt Fence
	Added 11/17/2014				
0150	503-C007		89	Linear Feet	Saw Cut, Full Depth
0160	603-CA005	(S)	235	Linear Feet	36" Reinforced Concrete Pipe, Class III
0170	606-B023		108	Linear Feet	Guard Rail, Remove and Replace Guard Rail & Posts
0180	606-E002		1	Each	Guard Rail, Terminal End Section, Flared
0190	609-D007	(S)	89	Linear Feet	Combination Concrete Curb and Gutter Type 2 Modified
0200	615-B001	(S)	5,055	Linear Feet	Precast Concrete Median Barrier
	Changed 11/14/2014				
0210	619-A1007		13,440	Linear Feet	Temporary Traffic Stripe, Continuous White, Type 1 Tape
0220	619-A2007		14,250	Linear Feet	Temporary Traffic Stripe, Continuous Yellow, Type 1 Tape
0230	619-D1001		250	Square Feet	Standard Roadside Construction Signs, Less than 10 Square Feet
0240	619-D2001		620	Square Feet	Standard Roadside Construction Signs, 10 Square Feet or More
0250	619-E1001		2	Each	Flashing Arrow Panel, Type C
0260	619-F3002		674	Each	Delineators, Median Barrier Mounted, Yellow
0270	619-G4001		256	Linear Feet	Barricades, Type III, Single Faced
0280	619-G5001		150	Each	Free Standing Plastic Drums
0290	619-G7001		68	Each	Warning Lights, Type "B"

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0300	619-J1002		2	Unit	Impact Attenuator, 50 MPH
0310	620-A001		1	Lump Sum	Mobilization
0320	627-C001		320	Each	Red-Clear Reflective Raised Markers
0330	682-A036		1,280	Linear Feet	Underground Branch Circuit, AWG 8, 3 Conductor
0340	684-A007		2	Cubic Yard	Pole Foundation, 30" Diameter
0350	686-A001		2	Each	Relocation of Existing Lighting Assemblies
0360	907-213-A001		2	Ton	Agricultural Limestone
0370	907-216-B004		3,270	Square Yard	Solid Sodding, Bermuda
0380	907-226-A001		1	Acre	Temporary Grassing
0390	907-230-A118		25	Each	Shrub Planting, Indian Hawthorn
0400	907-230-B047		8	Each	Tree Planting, Live Oak
0410	907-230-B087		25	Each	Tree Planting, Crape Myrtle
0420	907-233-A001		31	Cubic Yard	Tree Bark Mulch, Type III
0430	907-233-A002		47	Cubic Yard	Tree Bark Mulch, Type V
0432	907-237-A003		200	Linear Feet	Wattles, 20"
	Added 11/17/2014				
0434	907-246-B001		50	Linear Feet	Rockbags
	Added 11/17/2014				
0440	907-407-A001	(A2)	283	Gallon	Asphalt for Tack Coat
0450	907-618-A001		1	Lump Sum	Maintenance of Traffic
0460	907-619-E3001		5	Each	Changeable Message Sign
0470	907-626-A002		1	Mile	4" Thermoplastic Traffic Stripe, Skip White
0480	907-626-A003		2	Mile	6" Thermoplastic Traffic Stripe, Skip White
0490	907-626-C002		1	Mile	4" Thermoplastic Edge Stripe, Continuous White
0500	907-626-C004		1	Mile	6" Thermoplastic Edge Stripe, Continuous White
0510	907-626-F002		1	Mile	4" Thermoplastic Edge Stripe, Continuous Yellow
0520	907-626-F004		1	Mile	6" Thermoplastic Edge Stripe, Continuous Yellow
0530	907-626-G002		600	Linear Feet	Thermoplastic Detail Stripe, White, 4" Equivalent Length
0540	907-626-G003		210	Linear Feet	Thermoplastic Detail Stripe, Yellow, 4" Equivalent Length
0550	907-626-G004		500	Linear Feet	Thermoplastic Detail Stripe, White
0560	907-626-G005		100	Linear Feet	Thermoplastic Detail Stripe, Yellow
0570	907-626-H004		100	Linear Feet	Thermoplastic Legend, White
0580	907-682-E001		2	Each	Underground Junction Box With Concrete Pad
0590	907-699-A002		1	Lump Sum	Roadway Construction Stakes

ALTERNATE GROUP AA NUMBER 1

Line No.	Item Code	Adj Code	Quantity	Units	Description [Fixed Unit Price]
0600	907-304-F002	(GT)	330	Ton	Size 610 Crushed Stone Base ALTERNATE GROUP AA NUMBER 2
0610	907-304-F003	(GT)	330	Ton	3/4" and Down Crushed Stone Base ALTERNATE GROUP AA NUMBER 3
0620	907-304-F004	(GT)	330	Ton	Size 825B Crushed Stone Base ALTERNATE GROUP BB NUMBER 1
0630	907-403-A006	(BA1)	106	Ton	Hot Mix Asphalt, MT, 12.5-mm mixture ALTERNATE GROUP BB NUMBER 2
0640	907-403-M002	(BA1)	106	Ton	Warm Mix Asphalt, MT, 12.5-mm mixture ALTERNATE GROUP CC NUMBER 1
0650	907-403-A007	(BA1)	142	Ton	Hot Mix Asphalt, MT, 19-mm mixture ALTERNATE GROUP CC NUMBER 2
0660	907-403-M007	(BA1)	142	Ton	Warm Mix Asphalt, MT, 19-mm mixture ALTERNATE GROUP DD NUMBER 1
0670	907-403-A010	(BA1)	81	Ton	Hot Mix Asphalt, MT, 9.5-mm mixture ALTERNATE GROUP DD NUMBER 2
0680	907-403-M006	(BA1)	81	Ton	Warm Mix Asphalt, MT, 9.5-mm mixture Bridge Items
0688	907-810-D001 Added 11/05/2014	(S)	1	Each	Repairs to Knee Braces at Truss Contraction Joints
0690	907-824-A001		6	Each	Bridge Repair, Link Inspection
0700	907-824-A001		2	Each	Bridge Repair, Pin and Link Removal and Replacement
0710	907-824-A001		22	Each	Bridge Repair, Truss Monitoring