

## **PROPOSED IMPROVEMENTS TO SR 304 / I-269**

Marshall County, Mississippi

**State Project No. DB\STP-0029-03(009)/102556-304000**

### **QUESTIONS RECEIVED AS OF March 29, 2013**

- 35.** (We) respectfully request any utility drawings for the overhead power by Coldwater River?

**The available utility drawings will be posted to the project website.**

- 36.** In the RFP, the Target Project Completion Date is scheduled for approximately 9/5/15. It appears the project timeline was based on the original length of the D/B Coldwater River Bridge. Would MDOT consider extending the Target Project Completion Date based on the new length of bridge?

**No.**

- 37.** Per page 332, note 5, "Sag vertical curves may be located on a bridge if the low point of the vertical is at least 20 feet behind the bridge abutment."  
Is it the intention of this note to state that the low point of a sag vertical curve may not be located on the bridge? Please clarify?

**A sag low point may not be located on the bridge.**