

Mark C. McConnell
Deputy Executive Director/
Chief Engineer

Charles R. Carr
Director
Office of Intermodal Planning



Jackie Duckworth
Deputy Executive Director/
Administration

Willie Huff
Director
Office of Enforcement

Melinda L. McGrath
Executive Director

P. O. Box 1850 / Jackson, Mississippi 39215-1850 / Telephone (601) 359-7001 / FAX (601) 359-7110 / www.GoMDOT.com

Inter-Departmental Memorandum

Date: October 1, 2012

To: Roadway Design Division Design Team Leaders

From: Assistant Roadway Design Division Engineer
Richard Pittman *RP*

Subject: Alternate Asphalt Pay Items

In reference to the design memo dated April 6, 2010, Alternate Asphalt Pay Items, Construction Division has recently asked Roadway Design to revise the way the alternate items are shown on quantity sheets. Previously, designers were instructed to lump all Hot Mix Asphalt items together, and then lump all Warm Mix Alternates together. Designers are now instructed to list each asphalt item separately as an alternate pay item. See the attached example.

If there are any questions, please advise.

JRP:jrp

pc: Active Consultants
Roadway Design Division Engineer (Reese)
Roadway Design Section Engineers
Quality Control Engineer (Sutterfield)
Special Projects Engineer (Boteler)
Construction Division (Glenn)
District Engineers
LPA Division
Traffic Engineering Division



SUMMARY OF QUANTITIES (SHEET 1)

| PAY ITEM NO. | PAY ITEM | UNIT | PRELIMINARY | FINAL |
|--------------------------------|---------------------------------------|------|-------------|-------|
| *** CORRECT *** | | | | |
| ALTERNATE ASPHALT ITEMS | | | | |
| 907-403-A002 | HOT MIX ASPHALT, HT, 19-MM MIXTURE | TON | | |
| OR | OR | | | |
| 907-403-M011 | WARM MIX ASPHALT, HT, 19-MM MIXTURE | TON | | |
| 907-403-A006 | HOT MIX ASPHALT, MT, 12.5-MM MIXTURE | TON | | |
| OR | OR | | | |
| 907-403-M002 | WARM MIX ASPHALT, MT, 12.5-MM MIXTURE | TON | | |
| 907-403-A007 | HOT MIX ASPHALT, MT, 19-MM MIXTURE | TON | | |
| OR | OR | | | |
| 907-403-M007 | WARM MIX ASPHALT, MT, 19-MM MIXTURE | TON | | |
| *** INCORRECT *** | | | | |
| ALTERNATE ASPHALT ITEMS | | | | |
| 907-403-A002 | HOT MIX ASPHALT, HT, 19-MM MIXTURE | TON | | |
| 907-403-A006 | HOT MIX ASPHALT, MT, 12.5-MM MIXTURE | TON | | |
| 907-403-A007 | HOT MIX ASPHALT, MT, 19-MM MIXTURE | TON | | |
| OR | OR | | | |
| 907-403-M011 | WARM MIX ASPHALT, HT, 19-MM MIXTURE | TON | | |
| 907-403-M002 | WARM MIX ASPHALT, MT, 12.5-MM MIXTURE | TON | | |
| 907-403-M007 | WARM MIX ASPHALT, MT, 19-MM MIXTURE | TON | | |

MISSISSIPPI DEPARTMENT OF TRANSPORTATION
 1000 W. GULF BLVD., SUITE 1000, JACKSON, MISSISSIPPI 39201-1000
 601-977-1234
 8/11/2012 10:12 AM 508.45.DGN

| | | |
|--|---|--|
| MISSISSIPPI DEPARTMENT OF TRANSPORTATION SUMMARY OF QUANTITIES | |  WORKING NUMBER SQ-1 SHEET NUMBER |
| DATE: _____ DESIGN TEAM: _____ | FILENAME: _____ CHECKED: _____ DATE: _____ | |